

A scenic view of a rural landscape. In the foreground, there is a green field with a small pond and a fence. In the middle ground, there are several buildings, including a white church with a steeple. The background features rolling hills covered in dense green trees under a blue sky with light clouds.

Identifying Goals and Objectives for Watershed Restoration Projects



Justin Kauffman

-Project Manager

-Turnkey Environmental Solutions

-Design and Construction Services

www.rrrc1.com



Services

- Construction
- Design
- Consulting
- Permitting
- Nursery
- Planting
- Environmental Landscape
- E&S Control
- Construction Oversight and Management
- Invasive Species Control
- Site Assessment/Planning
- Stormwater Management

Native Nursery




Riparian Buffer Planting



Wetland Enhancement







Codorus Creek Watershed

Parallel Drainage Basin

⌘ 4 Major Branchs

- ⌘ Main
- ⌘ South
- ⌘ East
- ⌘ West

Most restoration has been completed in South and East Branch

Each Branch maintains unique parameters and must be addresses individually

Contributing Organizations

**Codorus Creek Watershed
Association**



**Izaak Walton League of
America**



Other Organizations



- WATERSHED ALLIANCE OF YORK
- YORK COUNTY CONSERVATION DISTRICT
- TROUT UNLIMITED, CODORUS CHAPTER
- YORK COUNTY PLANNING COMMISSION

**MANY OTHER LOCAL PARTIES HAVE
CONTRIBUTED OVER THE YEARS**

History of Codorus Restoration

{ The Turning Point

- ⌘ Legacy Sediments
- ⌘ Poor Sediment Transport
- ⌘ Accelerated Erosion Rates
- ⌘ Reduced Riparian Zone Density
- ⌘ Increased Runoff due to Urbanization and Agriculture
- ⌘ Poor Habitat and Biodiversity

Issues in the Watershed







Flood Damage from 2003 to
2004



-Circa 1990s

-Two Main Approaches to stream restoration

{ Replant Ripariain Zones
Use fish habitat structures to provide habitat and armor against erosion

Resulted in significant failure of one project site

Original Approach


- { Watershed Assessment
 - & Completed through 319 Grant
 - & Managed by ARRC President Lee Irwin
 - & Collected empirical data on all branches of watershed

- { WIP
 - & Watershed Implementation Plan
 - & Developed based on assessment
 - & Completed by York Co. Conservation District

Corrective Actions

- ⌘ Utilization of Fluvial Geomorphology, Floodplain Restoration, Hydraulic Engineering and Storm-water Management Techniques
- ⌘ Over 15+ Miles of Successful Restoration of East Branch and South Branch
- ⌘ Utilization of Conservation Practices in High Quality Areas of Watershed (i.e. West Branch)
- ⌘ Improved Fish Habitat and Recreation
- ⌘ Strong Community Involvement in Watershed
- ⌘ Increased Funding for Restoration Activities

Results



AQUATIC RESOURCE RESTORATION CO.
 10000 W. 100TH AVENUE, SUITE 100
 DENVER, COLORADO 80231
 (717) 428-9368 FAX: (717) 428-9411
 www.arsr.com
 A Complete Solution to Environmental Restoration



SCALE: 1"=20'
 DESIGNED BY: RJM/JM
 DRAWN BY: MEM/JM
 DATE: 13 FEB 2015
 PAGE: 2 of #

PERMIT PLAN - NOT FOR CONSTRUCTION



© 2015 Google

Google earth

Imagery Date: 9/6/2013 39°52'19.33" N 76°39'35.02" W elev 528 ft eye alt 2214 ft

{ Before



{ After



{ Before



{ After



{ Before



{ After









- ⌘ Better Understanding of Watershed
- ⌘ Identify Issues for Degradation and Constraints Governing Watershed
- ⌘ WIP Outlines Goals and Objectives of Restoration
- ⌘ Combats Typical Issues Faced by Sponsor Groups
- ⌘ Allows for Clear Communication Between Sponsors, Grant Coordinators and Consultants to Ensure Desired Results
- ⌘ Outlines Future Work

Reasons for Success

Most Importantly: Refined Views on Restoration



**EFFORTS BECAME LESS ABOUT FIGHTING
DEGRADATION AND MORE ABOUT
RESTORING THE WATER WAYS AND
FLOODPLAIN TO A CONDITION THAT COULD
HANDLE FLOW REGIMES WITHOUT
SHIFTING “EQUILIBRIUM”**

Benefits




Sponsors

- Able to maintain goals
- Focus on Conservation And Water Quality
- Improve Fishery and Habitat
- Sustain Involvement and Participation
- Increased productivity

Consultant

- Maintain consistent and uniform project approaches
- Gain and maintain data to evaluate success
- Learn and expand techniques new and old
- Increased productivity



Larue

Glen Rock

Google earth

© 2015 Google

1993

Imagery Date: 9/6/2013 39°48'13.05" N 76°44'38.49" W elev 548 ft eye alt 12380 ft

Incorporation of New Techniques



- New structures have been utilized
- Increased connection and efforts placed into floodplain areas
- Focus on wetlands for water management
- Development of diverse stream types and restoration approaches for unique situations
- More attention to project specific goals and incorporating them into design

A photograph of a river with a stone-lined bank. The water is calm and reflects the surrounding landscape. The bank is covered with mossy rocks and some dry vegetation. In the background, a white truck is parked on a grassy area, and there are trees and a hillside. The text "Old Techniques" is overlaid in yellow.

Old Techniques






FIGURE 8-22. Cross-Vane Structure.




FIGURE 8-23. J-Hook Vane.




FIGURE 8-25. Native material bank revetment. [Kosgen, 1993a]




FIGURE 8-24. Native material bank revetment. [Rosgen, 1993a]



FIGURE 8-26. "W" rock weir. [Rosgen, 1993a]




FIGURE 8-27. Log-vane bank feature. [Rosgen, 1993a]









Questions?